

BOQ

SBICAP SECURITIES				DATE	28.12.2020
SL	ITEM DESCRIPTION	UNIT	QTY	RATE	AMOUNT
1.	Providing and laying new carpet of 2.5/3 mm thk. Nylon in blue colour in office area complete with required material and shade as per approved.	Sqft.	2000		
2.	WOODWORK				
a	<p>DOORS - Fully glazed door (Cabins) size-6.5'x2.5'</p> <p>Providing fixing 4" plywood frame fully glazed 12mm thk toughened float glass fixed with necessary patch fittings (Dorma make) including cutting, making holes, cutouts in the glass of required shape and size to accommodate fittings and fixing the fittings in floors, soffits, jams including necessary fixtures, screws, sealant wherever required and SS cover over patch fittings. Rate shall include necessary etching film / LOGO, approved patch fitting locking systems, 1 pair of 300 mm long S. S. (H Shape) Handles of approved make, floor springs, and any necessary hardware items.</p>	No.	4		
b	<p>PARTITIONS</p> <p>Laminate finish (Both sides)</p> <p>Providing and fixing of 6mm plywood with ISI mark, Grade/Quality - 710 BWP marine plywood, brand - Green ply/Aeon/Swadesh/similar with 1mm laminate finish (Brand - Rotolam/similar) on both sides of the partition, with white and blue combination. Till 4 ft. height the partition will be of plywood, from 4 ft. height till 8 ft. 12 mm toughened glass will be provided. Providing aluminum channel in between partition at 2 feet interval with one channel horizontally placed at the top and the bottom, brand - Jindal/similar, aluminum channel size - 63.5 X 38.1X1.2 mm thk. Doing proper workmanship on site and dark brown polish work to edges and joints as per required.</p>	Sq.ft.	1500		
c	<p>WORK STATIONS</p> <p>Work stations (size" 3'-.6"x2'-0") made with plywood with ISI mark, Grade/Quality - 710 BWP marine plywood, brand - Greenply/Aeon/Swadesh/similar with 1mm laminate finish (make - Rotolam/similar). incl. dark brown polish on inside surfaces, drawer channels, drawers all necessary hardware complete. Work station top, front and side legs to be made with 19 mm plywood of the above mentioned grade and brand. Work station edge will be finished with PVC edge binding. Each work station to have a 3 drawer set, sizing - 16"x29"x24". The side panels, top and bottom of drawer set to be made with 19 mm plywood, 1mm white laminate finish to be given on each side of the drawer. Each drawer front to</p>	No.	49		

	be made with 19 mm plywood with 1 mm white laminate finish, inside drawers 12 mm plywood to be used. All drawers will have dark brown polish inside. Each drawer channels will have a set of telescopic channels for its free movement, channel brand - Hafele/Hettich/EBCO. Each work station to have a MS Powder coated Keyboard tray and 50mm Dia MS wire manager of approved quality.			
d	Work Station For Cabin in laminate finish Providing and fixing Officer Table of size 5' x 2.5' x 2.5' high to detail as shown in drawing to be made with plywood with ISI mark, Grade/Quality - 710, brand - Greenply/Aeon/Swadesh/similar with 1mm laminate finish (Brand - Rotolam/similar). Table top, two side legs and front to be made with 19mm plywood with 1 mm laminate finish. Side table storage unit sizing - 36"x16"x29". Storage top, front and the two side to be made with 19mm Plywood with 1 mm laminate finish. The side table storage to have two drawers and two doors, each sizing 18"x5", 18"x19" respectively. Drawers and doors to be made with 19 mm plywood with 1mm laminate finish from the outside, inner portion to be polished dark brown. the drawers to have telescopic channel, brand - Hafele/Hettich/EBCO/similar, hinges, locks, magnet, etc complete as required. MS Powder coated Keyboard tray and 50mm Diameter MS wire manager of approved quality.	No.	2	
e	Overhead storage unit Overhead storage to be made with plywood with ISI mark, Grade/Quality - 710, make- Greenply/Aeon/Swadesh/similar with 1mm laminate, make - Rotolam/similar. The top, bottom, front and back of the storage to be made with 19 mm plywood. Outer part of the storage to have white colour laminate finish. The inner portion will have dark brown polish. The storage to have groove at the bottom for opening/closing the door. Cost is inclusive of magnets, hinges, locks and all necessary hardware complete.	Sq.ft.	300	
f	Centre table for sofa, size - 36"x24"	No.	1	
g	corner table for sofa, size - 36"x18"	No.	1	
h	Conference Table in Laminate Finish 8 Seater Conference table (size - B35 to be made with plywood with ISI mark, Grade/Quality - 710 BWP marine plywood, make- Greenply/Aeon/Swadesh/similar with 1mm laminate, brand - Rotolam/similar. Table top to be made 1.5" thick with 19 mm plywood with 1 mm laminate finish. The legs of the conference table to be made with 19 mm plywood and 1mm laminate finish as per drawing. The table to have plug points and socket, Roma make, at the horizontal center leg of the table.	No.	1	

i	<p>Reception table in Laminate finish</p> <p>Reception table (size" 7' x 2.5' x 2.5') made with plywood with ISI mark, Grade/Quality - 710 BWP marine plywood, brand - Greenply/Aeon/Swadesh/similar with 1mm laminate finish (Brand - Rotolam), complete incl. dark brown polish on inside surfaces, drawer channels, drawers as /design, all necessary hardware complete. Reception table to have a 3 drawer set, sizing - 16"x29"x24". The side panels, top and bottom of drawer set to be made with 19 mm plywood, 1mm white laminate finish to be given on each side of the drawer. Each drawer front to be made with 19 mm plywood with 1 mm white laminate finish, inside drawers 12 mm plywood to be used. All drawers will have dark brown polish inside. Each drawer channels will have a set of telescopic channels for its free movement, channel brand - Hafele/Hettich/EBCO. 2 pcs MS Powder coated Keyboard tray for two people on each side of the table and 2 pcs 50mm Diameter MS wire manager of approved quality.</p> <p>SUB TOTAL OF WOOD WORK</p>	No.	1	
3	<p>PAINTING</p> <p>Plain painting without putty - Two coats of plastic emulsion paint to be applied on wall / ceiling using roller brush, after levelling the surface and applying one coat of primer. Berger/Asian.</p> <p>SUB TOTAL OF PAINTING</p>	Sq.ft.	4500	
4	<p>GYP SUM CEILING REPAIRING WOK</p> <p>For replacing old lights with new ones.</p>	Sq.ft.	2000	
5	<p>MISCELLANEOUS</p>			
a	5 Seated sofas for reception area	No.	1	
b	P/f. Roller blinds for windows and external glazing.	Sq.ft.	450	
c	P/f. New soft board for work station.	Sq.ft	350	
6	<p>PANTRY WORK</p> <p>Granite counter, Jet Black/Galaxy Black/R Black, size 8'x2'. Pantry counter to be made with 1" thick granite with support of 3 black stones under the granite using Ambuja cement. The storage below pantry to be made with plywood with ISI mark, Grade/Quality - 710, brand - Greenply/Aeon/Swadesh/similar with 1mm laminate finish (Brand - Rotolam/similar).Storage provision below granite counter. Below granite storage is to be made with 19 mm plywood shelf placed horizontally, 0.8mm laminate finish, sizing - 8'x20". The door for the</p>	Rft.	8	

storage to be made 19 mm blackboard with laminate finish.				
---	--	--	--	--

ELECTRICAL WORK

SBICAP SECURITIES				Date	28.12.2020
Sl.	Particulars	Units	Qty	Rate	Amount
1	LED Panel Light 15 Watt Round White Make- Mescab	No.	42		
2	Wiring of Sub main & Power Point For electrical Plug Point (UPS & Raw Power) Including Supply of 4 Sq MM single core Cable & PVC Conduit/Cashing. Make - Mescab.	Point	170		
3	Wiring of Electrical Light, Exhaust Fan & Bell Point Including Supply of 1.5 Sq MM Cable with PVC Conduit / Cashing. Make - Mescab.	Point	50		
4	Earthing Copper Cable 1.5 Sq MM for UPS & Raw Power. Make - Mescab.	Mtr.	450		
5	6 Way Modular Face Plate Including 2 Nos Modular Switch & 3 Nos Modular Socket Make- Anchor ROMA / Other Standard	Set	56		
6	2 Way Modular Face Plate Including 2 Nos Modular Switch Make- Anchor ROMA / Other Standard	Set	5		
7	Labour Charges for LED Panel Light fitting With False Ceiling Cutting & Connection	Nos	42		
	TOTAL				

NETWORKING & CABLING

SBICAP SECURITIES				Date	28.12.2020
Sl.	Particulars	Unit	Qty	Rate	Amount
1	Data Cat-6 UTP Cable For Data & Telephone Point Make- D-Link/Digi link	Mtr.	2000		
2	2 Pair Telephone wire.	Mtr.	2000		
3	2 Way face Plate with I/O for Data & Telephone For Data & Telephone Point Including Back Box Make- D-Link/Digilink	No.	56		
4	24 Port Patch Panel Cat-6 Make- Digisol/D-link/Digilink	No.	3		
5	Patch Cord RJ-45 Connector; Cat-6 , Length 2 Meter For Data Point Make- Digisol/D-link/Digilink	No.	56		
6	Patch Cord RJ-45 Connector; Cat-6 , Length 1 Meter For Data Point Make- Digisol/D-link/Digilink	No.	56		
7	100 Pair MDF Box with krone	No.	1		
8	PVC Conduit/Cashing Upto 38MM	Mtr.	500		
9	Laying Charges of Cat-6 Cable through PVC Conduit & cashing	Mtr.	3965		
10	Installation Charges for Patch Panel & Krone with Crimping & I/O Installation with Crimping & testing	L/s	1		
	TOTAL				